



BUILDER SERIES PRODUCT GUIDE

A SIMPLE PACK FOR EVERY RIDGE-SLOT PROJECT

Preformed 27-gauge galvanized-steel mesh panels with 1/8 x 1/8-in. openings, made for consistent estimating, staging and installation beneath a compatible continuous ridge vent.

SKU	PANELS	PLANNING COVERAGE	BEST FIT	MSRP
RA1	1	47 in. / 3.9 ft	Top-off, sample or repair	\$19.99
RA25	7	27.4 ft	Small roof or short ridge run	\$139.99
RA50	13	50.9 ft	Typical reroof or new build	\$259.99
RA100	26	101.8 ft	Large roof or multi-run project	\$519.99

CHOOSE BY PROJECT FOOTAGE: use RA1 as a top-off panel, RA25 for short runs, RA50 for typical projects and RA100 for larger roofs.



Actual RidgeArmor field installation. RidgeArmor protects the structural ridge slot before the separate compatible continuous ridge vent and cap are installed.

DEFINED TAKEOFF

Countable panels and clear pack coverage simplify estimating.

JOB-READY FORMAT

Preformed panels replace cutting and shaping loose roll mesh on the roof.

PROJECT SUPPORT

FireTek can help confirm panel counts from a roof plan or ridge footage.

Coverage is a planning value based on 47-in. panels. Final takeoffs must include the specified 1/2-in. overlap at panel joints and required end coverage. Confirm the adopted code, project scope and compatible ridge-vent assembly before ordering.